



Page: 1 of 3

Supersedes: 11-Feb-2019

Effective: 10-Mar-2023

1.0 Purpose

This procedure establishes calibration requirements for TIG (GTAW) weld machines located at Meyer Tool, Inc. facility at 3055 Colerain Avenue, Cincinnati, Ohio.

2.0 Reference Documents

- 2.1 AWS D17.1 Specification for Fusion Welding for Aerospace Applications
- 2.2 GE P8TF3 or P8TF11 Shielded Arc Welding
- 2.3 Honeywell WBS 5018 Fusion Arc Welding
- 2.4 QP-118 Fusion Welding
- 2.5 Pr-4010
- 2.6 DMP 43-001
- 2.7 MTI-168 Machine Preventative Maintenance Form

3.0 Responsibility

- 3.1 The Quality Department has the prime responsibility for operation of the Calibration system.

4.0 Calibration Procedure

- 4.1 Calibration is performed by an outside vendor or the MTI calibration department to the requirements listed in section 5.0.

5.0 TIG (GTAW) Welder Calibration

- 5.1 **Amperage:** All fusion (TIG) welding equipment shall be calibrated from the following set points:
 - 5.1.1 15, 45, and 75, deviation of +/- 1.5%
- 5.2 **Volts:** All fusion (TIG) welding equipment shall be calibrated from the following set point:
 - 5.2.1 12 VDC, deviation of +/- 2.0 VDC
- 5.3 **GAS Flow Meters/Regulators:** All Gas Flow Meters shall be calibrated from the following range(s):
 - 5.3.1 5-20 CFH, deviation of +/- 2.5 CFH

Date		Date	
Prepared by	TERESA TEPE	Approved	BRIDGET NOLAN

This document and the information contained within is the property of Meyer Tool, Inc. Any reproduction, disclosure, or uses of the information within this document are prohibited except authorized in writing by Meyer Tool, Inc. The recipient accepts the responsibility for maintaining the confidentiality of the contents of this document.



6.0 Records

- 6.1 All records will be maintained in accordance with PI-166 Records Control, applicable customer requirements.

Revision History

[illegible]